



## **Audio Visual Equipment**

### **Audio**

#### **Microphones**

There is 1 x handheld radio microphone and 2 x lapel microphones.

In addition to the radio microphones 3 x cabled microphones are available for use by those without access to the radio microphone; these xlr connections will be installed in the floor boxes

#### **Line inputs**

2 x line inputs are available for the connection of a CD player, phone or MP3 player.

One is located in a floor box and one in the cabinet

#### **Speakers**

4 x Apart Mask6C speakers are installed on the 1st and 3rd beam just above the corbel, to give good coverage of the main body of the church. Two Mask4C speakers have also been installed at the 4th beam to cover the gallery.

#### **Induction loop**

A new induction loop is available to cover the whole building.

### **Visual**

#### **Projection Screen**

A projector screen, measuring 2.4 metres wide by 1.5 metres high is mounted on the wall to the left side of the arch and can be electrically lowered.

#### **Projector**

A projector is positioned on the beam and operated from the main console.

#### **Inputs**

2 x inputs have been installed for connection of a laptop; one at the rear of the church next to the power points in the kitchen and one in the floor box nearest to the organ.